



City of Colorado Springs

**ADDENDUM #2
Q24-087 PB
08/23/2024**

NAME OF PROJECT: TRANSIT MAIN GATE REPLACEMENT

PROPOSAL DUE DATE: HAS BEEN EXTENDED TO: FRIDAY, SEPTEMBER 6, 2024 - NO LATER THAN 5:00 PM MST

This document shall become as fully a part of the above named solicitation and Contract Documents as if included and shall take full and complete precedence over anything stated or shown to the contrary in them.

Acknowledgment: Each Offeror shall indicate in the place provided acknowledgment of receipt of this Addendum.

Each and every Offeror, subcontractor, and material supplier shall be responsible for reading each and every item in this Addendum to ascertain the extent and manner it affects the work in which he is interested.

*****CHANGES TO THE PUBLICATION NOTICE*****

The following items and information are corrections and additions to the above referenced project.

- 1. PROPOSAL DUE DATE HAS BEEN EXTENDED TO FRIDAY, SEPTEMBER 6, 2024 - NO LATER THAN 5:00 PM MST**
- 2. UPDATED SCOPE OF WORK TO INCLUDE INSTALLATION OF KEYPAD LOCK FOR THE EXISTING PEDESTRIAN GATE LOCATED AT 1190 TRANSIT DR.**
- 3. UPDATED PRICE SHEET**

Offeror shall acknowledge receipt of this addendum by signing below, and this addendum must be returned as part of the proposal.

Signature

Date

Firm

1015 Gate Replacement Project Scope of Work

Project Overview

The City of Colorado Springs Transit Services, DBA Mountain Metropolitan Transit (MMT), would like to receive quotes for the removal and replacement of the Transit administration main front entry gate, remove and install (1) new pedestrian gate and install (1) new pedestrian gate, located at 1015 Transit Dr. and **the installation of a keypad lock for the existing pedestrian gate located at 1190 Transit Dr.**

Period of Performance

Period of performance for this project is 45 days from issuance of the Notice to proceed.

Scope Of Work

Main Entry Gate located at 1015 Transit Dr.

1. Contractor shall perform site walk to determine final measurements.
2. Contractor shall remove and recycle existing sliding gate assembly and associated hardware, except for the gate opener.
3. Contractor shall fabricate or provide a new sliding gate assembly mounted within the existing gate parameters, utilizing the existing gate opener.
 - a. The existing opening is approximately 32 feet.
 - b. Gate shall be made of steel or aluminum construction, reinforced to prevent sagging.
 - c. Gate shall be decorative metal design to match or closely match existing fencing.
 - d. Gate assembly and associated components such as guideways shall be powder coated black.
 - e. Gate assembly shall have bright reflective safety tape making the gate visible in the closed position to outside and/or inside traffic.
 - f. Gate assembly shall be made up of serviceable parts such as rollers, guides, and associated hardware.
 - g. Gate assembly shall include all necessary safety switches and sensors.
4. Contractor shall supply all design, materials, supplies, hardware, labor, transportation, and disposal.

Pedestrian Gates located at 1015 Transit Dr.

1. Remove existing pedestrian gate and install new decorative gate assembly with push button keypad entry locking mechanism. Estimate to include posts, installation, and necessary hardware.
2. Remove existing fence panel and install new decorative pedestrian gate assembly with push button keypad locking mechanism. Estimate to include posts, installation, and necessary hardware.

Pedestrian Gate located at 1190 Transit Dr.

1. Furnish and install a keypad locking mechanism to the existing pedestrian gate on the East side of the facility.

Warranty

1. Gate and gate hardware shall carry a 2-year parts and labor warranty, covering workmanship defects.

1015 Transit Administration Gate Replacement Project

Price Sheet – Updated 08/23/24

Item	Cost
New decorative main vehicle gate installed	\$
Labor to remove existing vehicle gate	\$
Misc Parts and Consumables	\$
Remove and replace existing pedestrian gate w/push button combo lock assembly.	\$
Remove existing fence panel and install new pedestrian gate assembly w/push button combo lock assembly.	\$
Equipment Rental Costs	\$
New keypad retrofit for existing pedestrian gate at 1190 Transit Dr.	\$
TOTAL COST OF PROJECT	\$